GENERAL SUMMARY

ITEM	TOTAL	UNIT	DESCRIPTION	M.P. 104.3	M.P. 106.1	M.P. 106.8	M.P. 107.5
			GENERAL				
IB.ART.6	LUMP	LUMP SUM	PREMIUM FOR CONTRACT PERFORMANCE BOND AND PAYMENT BOND	LUMP	LUMP	LUMP	LUMP
SP 614	LUMP	LUMP SUM	MAINTAINING TRAFFIC	LUMP	LUMP	LUMP	LUMP
SP 614ZP	160	HOURS	ZONE PERSON WITH ZONE VEHICLE	40	40	40	40
SP 619	LUMP	LUMP SUM	FIELD OFFICE	LUMP	LUMP	LUMP	LUMP
SP 623	LUMP	LUMP SUM	CONSTRUCTION LAYOUT SURVEY	LUMP	LUMP	LUMP	LUMP
624	LUMP	LUMP SUM	MOBILIZATION	LUMP	LUMP	LUMP	LUMP
			ROADWAY				
201	LUMP	LUMP SUM	CLEARING AND GRUBBING	LUMP	LUMP	LUMP	LUMP
202	4846	FOOT	GUARDRAIL REMOVED	275	1810	1475	1286
202	16	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A	4	4	4	4
202	284	FOOT	CURB REMOVED	54	84	66	80
202	16	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	4	4	4	4
202	3	EACH	CATCH BASIN REMOVED		1	2	
202	311	SQ. YD.	APPROACH SLAB REMOVED		100	112	99
203	3334	CU. YD.	EXCAVATION	110	1252	1229	743
203	4433 3	CU. YD.	EMBANKMENT	85	1723 3	1230 3	1395
204	13576	SQ. YD.	SUBGRADE COMPACTION	771	3955	5877	2973
SP 302	1870 2	CU. YD.	ASPHALT CONCRETE BASE	81 2	582	780	427
SP 304	2073	CU. YD.	AGGREGATE BASE	126	648	807	492
407	1322	GALLON	NON-TRACKING TACK COAT	83	400	542	297
441	540	CU. YD.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22	34	163	220	123
441	357	CU. YD.	ASPHALT CONCRETE SURFACE COURSE. TYPE 1, PG64-22	25	117	126	89
441	34	CU. YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, 449 (DRIVEWAYS)		2	32	
601	535	SQ. YD.	CRUSHED AGGREGATE SLOPE PROTECTION, AS PER PLAN		130	205	200
601	6.6	CU. YD.	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	2.2		2.2	2.2
605	985	FOOT.	AGGREGATE DRAINS			985	
606	2108	FOOT	GUARDRAIL, TYPE MGS	275	308	1475	50
606	3054	FOOT	GUARDRAIL, TYPE MGS WITH LONG POSTS		1854		1200
606	16	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	4	4	4	4
606	14	EACH	ANCHOR ASSEMBLY, TYPE E	4	4	2	4
606	3	EACH	ANCHOR ASSEMBLY, TYPE T			3	
609	255	FOOT	CURB, TYPE 6	25	84	66	80
617	102	CU. YD.	COMPACTED AGGREGATE	9	27	48	18
621	41	EACH	RPM		20	21	
638	4	EACH	WATER VALVE BOX ADJUSTED TO GRADE			2	2
638	1	EACH	FIRE HYDRANT ADJUSTED TO GRADE			1	
642	1.33	MILE	EDGE LINE, 4", TYPE 1		0.69	0.64	
642	0.93	MILE	CENTER LINE, TYPE 1		0.35	0.32	0.26
642	42	FOOT	STOP LINE, TYPE 1		20	22	
659	15485 3	SQ. YD.	SEEDING AND MULCHING	464	4093 3	4653	6275
659	1543	CU. YD.	TOPSOIL	70	369	400	704
690	3	EACH	SPECIAL - MAILBOX REMOVED AND RESET		1		2
832	20,000	EACH	EROSION CONTROL	5000	5000	5000	5000

NO.	REVISIONS	BY	DATE
2	QUANTITY REVISIONS	DRP	10/11/23
3	QUANTITY REVISIONS	DRP	10/16/23

DESIGNED DRP | CHECKED DCA
DRAWN DRP | IN CHARGE SMK

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue - Suite 2100 | Cleveland, OH 44114 (216)861-0200 www.osborn-eng.com
1201 East Market Street - Suite 200 | Akron, OH 44305 (330)435-3132

OHIO TURNPIKE

GENERAL SUMMARY
M.P. 104.3, 106.1, 106.8, AND 107.5 SANDUSKY AND ERIE COUNTIES

PROJECT 43-24-05
DATE: 06/30/23

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

General Summary.dwg: 10/17/23 - 6:29am

GENERAL SUMMARY

ITEM	TOTAL	UNIT	DESCRIPTION	M.P. 104.3	M.P. 106.1	M.P. 106.8	M.P. 107.5
			DRAINAGE				
SPECIAL	6	EACH	12" PRECAST END SECTION	2		2	2
SP 611	152	FOOT	12" CONDUIT, TYPE B	44		59	49
SP 611	2 274	FOOT	12" CONDUIT, TYPE F	2 102		89	83
SP 611	3	EACH	CATCH BASIN, NO. CB-1		1	2	
SP 611	13	EACH	CATCH BASIN RECONSTRUCTED TO GRADE, 4" TO 12"	4	3	2	4
SP 611	7	EACH	CATCH BASIN, NO. CB-1, GRATE AND CASTING	2	2	1	2
			MAINTENANCE OF TRAFFIC				
614	4	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)			4	
614	22	EACH	BARRIER REFLECTOR, TYPE 1 (SPACED @ 50' c/c MAX.)			22	
614	22	EACH	OBJECT MARKER, ONE WAY (SPACED @ 50' c/c MAX.)			22	
614	0.19	MILE	WORK ZONE CENTER LINE, CLASS I, 740.06, TYPE I			0.19	
614	0.62	MILE	WORK ZONE EDGE LINE, CLASS I, 4", 642 PAINT (WHITE)			0.62	
614	0.71	MILE	WORK ZONE EDGE LINE, CLASS I, 4", 740.06, TYPE 1 (WHITE)			0.71	
614	20	FOOT	WORK ZONE STOP LINE, CLASS I, 740.06, TYPE 1			20	
614	40	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE			40	
SP 614C	1942	FOOT	REMOVAL OF PAVEMENT MARKINGS			1942	
615	423	SQ. YD.	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A			423	
SP 622	840	FOOT	PORTABLE BARRIER (WITHOUT GLARE SCREEN)			840	
SP 622	200	CU. YD.	PORTABLE BARRIER, BRIDGE MOUNTED			200	
			STRUCTURES				
SP 202	LUMP	LUMP SUM	PORTIONS OF STRUCTURE REMOVED	LUMP	LUMP	LUMP	LUMP
509	800	POUND	REINFORCING STEEL, REPLACEMENT OF EXISTING REINFORCING STEEL	200	200	200	200
SP 509	261,957	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60	62969	62977	71458	64553
510	2060	EACH	DOWEL HOLES WITH NON-SHRINK, NON-METALLIC GROUT	528	472	590	470
SP 511 (QC2)	645	CU. YD.	QC2 CONCRETE, SUPERSTRUCTURE DECK SLAB	155	155	180	155
SP 511 (QC2)	2 257	CU. YD.	QC2 CONCRETE, BARRIERS AND PARAPET	65	2 64	65	2 63
SP 511 (QC2)	2 166	CU. YD.	QC2 CONCRETE, ABUTMENT SLAB	2 37	2 41	2 47	2 41
511	40	CU. YD.	CLASS QC1 CONCRETE, PIER CAP	5	10	10	15
511	20	CU. YD.	CLASS QC1 CONCRETE, ABUTMENT	5	5	5	5
513	2 4185	EACH	WELDED SHEAR STUD CONNECTORS	2 2427	2 132	2 1538	88
513	2 17	EACH	2 STRUCTURAL STEEL MISC.: REMOVE AND REINSTALL EXISTING CROSSFRAMES			2 17	
516	LUMP	LUMP SUM	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN	LUMP	LUMP	LUMP	LUMP 1
SP 516A	8	FOOT	CRACK REPAIR USING EPOXY INJECTION		8		
SP 516B	2070	FOOT	SEALING OF CONSTRUCTION JOINTS	510	500	505	555
SP 516G	80	EACH	REPLACE EXPANSION BEARING DEVICE	20	20	20	20
SP 516J	60	EACH	REPLACE FIXED BEARING DEVICE	15	15	15	15
SP 519	1215	SQ. FT.	PATCHING OF CONCRETE STRUCTURES	58	362	560	235
526	3 392	SQ. YD.	REINFORCED CONCRETE APPROACH SLABS (T=12")	3 91	3 98	3 107	3 96
SP 527	LUMP	LUMP SUM	FALSEWORK, TEMPORARY BRACING AND PROTECTIVE STRUCTURES	LUMP	LUMP	LUMP	LUMP
SP 533	242	FOOT	3" CONTINUOUS STRIP SEAL IN STRUCTURAL STEEL JOINT	57	60	67	58
SP 533	242	FOOT	1 ½" ELASTOMERIC COMPRESSION SEAL IN STRUCTURAL STEEL JOINT	57	60	67	58
SP 536	3930	SQ. YD.	CONCRETE WEATHERPROOFING, DECK, ABUTMENT SLABS, AND APPROACH SLABS	960	935	1075	960
SP 536	1555	SQ. YD.	CONCRETE WEATHERPROOFING, BARRIERS AND PARAPETS	370	360	390	435
SP 536	1280	SQ. YD.	CONCRETE WEATHERPROOFING, SUBSTRUCTURE	315	315	335	315
SP 607	1705	FOOT	TYPE II FENCE, ALL ALUMINUM (6'-0" CHAIN LINK WITH SPECIALS)	425	400	415	465

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue - Suite 2100 | Cleveland, OH 44114 (216)481-0200 www.osborn-eng.com
1201 East Market Street - Suite 200 | Akron, OH 44305 (330)435-3132

NO.	REVISIONS	BY	DATE
1	ADDED PAY ITEM	MD	10/2/23
2	REVISED QUANTITIES	DRP	10/11/23
3	REVISED QUANTITIES	MD	10/16/23

DESIGNED DRP | CHECKED DCA
DRAWN DRP | IN CHARGE SMK

GENERAL SUMMARY
M.P. 104.3, 106.1, 106.8, AND 107.5 SANDUSKY AND ERIE COUNTIES

PROJECT 43-24-05
DATE: 06/30/23

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

General Summary.dwg: 10/16/23 - 9:20am



SECTION A-A



SECTION B-B

FINAL SLAB ELEVATIONS		
POINT	REAR ABUTMENT	FORWARD ABUTMENT
A	684.01	681.39
B	684.23	681.61
C	684.01	681.39
D	683.86	681.24
E	684.25	681.59
F	683.86	681.24

NOTES:

1. FOR CHAIN LINK FENCE DETAILS, SEE OTIC STANDARD DRAWING CL-2.
2. FOR DECK JOINT DETAILS, SEE OTIC STANDARD DRAWINGS DJ-1, DJ-2, AND DJ-5.

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue - Suite 2100 | Cleveland, OH 44114 (216)481-0200
www.osborneng.com
1201 East Market Street - Suite 200 | Akron, OH 44305 (330)435-5132

NO.	REVISIONS	BY	DATE
3	OPTIONAL CJ	MD	10/16/23
-	-	-	-
-	-	-	-

DESIGNED	CHECKED
JDH	EJW
DRAWN	IN CHARGE
MJD	SMK

COPP ROAD ABUTMENT PLAN - 2
COPP ROAD OVER OHIO TURNPIKE
SANDUSKY COUNTY
M.P. 104.3

PROJECT 43-24-05
DATE: 06/30/23

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

MP 104.3 - Abutment Plan.dwg; 10/16/23 - 4:41pm

MP 106.1 Cross Sections.dwg; 10/16/23 - 2:18pm



Sheet Totals	Cut	Fill
Seeding	474	164
	118	

51 / 141	PROJECT 43-24-05	NW/SW ROAD CROSS SECTIONS	DESIGNED MA	CHECKED DCA	NO.	REVISIONS	BY	DATE	DESIGN AGENCY		
	DATE: 06/30/23	NORTHWEST/SOUTHWEST ROAD OVER OHIO TURNPIKE	DRAWN MA	IN CHARGE SMK	3	QUANTITY REVISIONS	MA	10/16/23	OSBORN ENGINEERING	1111 Superior Avenue - Suite 2100 | Cleveland, OH 44114 (216)-861-2020 www.osborn-eng.com	
		M.P. 106.1 SANDUSKY AND ERIE COUNTIES			-	-	-	-		1201 East Market Street - Suite 200 | Akron, OH 44305 (330)-535-3132	

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE

MP 106.1 Cross Sections.dwg; 10/16/23 - 2:22pm



Sheet Totals	Cut	Fill
Seeding	515	127	205

52
141

PROJECT 43-24-05

DATE: 06/30/23

NW/SW ROAD CROSS SECTIONS

NORTHWEST/SOUTHWEST ROAD OVER OHIO TURNPIKE

M.P. 106.1 **SANDUSKY AND ERIE COUNTIES**

DESIGNED	CHECKED
MA	DCA
DRAWN	IN CHARGE
MA	SMK

NO.	REVISIONS	BY	DATE
3	QUANTITY REVISIONS	MA	10/16/23
-	-	-	-
-	-	-	-

DESIGN AGENCY

OSBORN ENGINEERING

1111 Superior Avenue • Suite 2100 | Cleveland, OH 44114 (216)-861-2020 www.osborn-eng.com

1201 East Market Street • Suite 200 | Akron, OH 44305 (330)-535-3132

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE

MP 106.1 Cross Sections.dwg; 10/16/23 - 2:25pm



Sheet Totals	Cut	Fill
Seeding	98	120
280		

53
141

PROJECT 43-24-05

DATE: 06/30/23

NW/SW ROAD CROSS SECTIONS

NORTHWEST/SOUTHWEST ROAD OVER OHIO TURNPIKE

M.P. 106.1 **SANDUSKY AND ERIE COUNTIES**

DESIGNED	CHECKED
MA	DCA
DRAWN	IN CHARGE
MA	SMK

NO.	REVISIONS	BY	DATE
3	QUANTITY REVISIONS	MA	10/16/23
-	-	-	-
-	-	-	-

DESIGN AGENCY

OSBORN ENGINEERING

1111 Superior Avenue • Suite 2100 | Cleveland, OH 44114 (216)-861-2020 www.osborn-eng.com

1201 East Market Street • Suite 200 | Akron, OH 44305 (330)-535-3132

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE

MP 106.1 Cross Sections.dwg; 10/16/23 - 2:28pm



Sheet Totals	Cut	Fill
Seeding	44	99
301		

54
141

PROJECT 43-24-05

DATE: 06/30/23

NW/SW ROAD CROSS SECTIONS
NORTHWEST/SOUTHWEST ROAD OVER OHIO TURNPIKE
M.P. 106.1 **SANDUSKY AND ERIE COUNTIES**

DESIGNED	CHECKED
MA	DCA
DRAWN	IN CHARGE
MA	SMK

NO.	REVISIONS	BY	DATE
3	QUANTITY REVISIONS	MA	10/16/23
-	-	-	-
-	-	-	-

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue • Suite 2100 | Cleveland, OH 44114
(216)-861-2020
www.osborn-eng.com
1201 East Market Street • Suite 200 | Akron, OH 44305
(330)-535-3132

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE

MP 106.1 Cross Sections.dwg; 10/16/23 - 2:31pm



Sheet Totals	Fill	Cut	Seeding
	221	97	602

55
141

PROJECT 43-24-05

DATE: 06/30/23

NW/SW ROAD CROSS SECTIONS
NORTHWEST/SOUTHWEST ROAD OVER OHIO TURNPIKE
M.P. 106.1 **SANDUSKY AND ERIE COUNTIES**

DESIGNED	CHECKED
MA	DCA
DRAWN	IN CHARGE
MA	SMK

NO.	REVISIONS	BY	DATE
3	QUANTITY REVISIONS	MA	10/16/23
-	-	-	-
-	-	-	-

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue • Suite 2100 | Cleveland, OH 44114
(216)-861-2020
www.osborn-eng.com
1201 East Market Street • Suite 200 | Akron, OH 44305
(330)-535-3132

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE

MP 106.1 Cross Sections.dwg; 10/16/23 - 2:35pm



Sheet Totals	Cut	Fill
Seeding	445	126	221

56
141

PROJECT 43-24-05

DATE: 06/30/23

NW/SW ROAD CROSS SECTIONS

NORTHWEST/SOUTHWEST ROAD OVER OHIO TURNPIKE

M.P. 106.1 **SANDUSKY AND ERIE COUNTIES**

DESIGNED	CHECKED
MA	DCA
DRAWN	IN CHARGE
MA	SMK

NO.	REVISIONS	BY	DATE
3	QUANTITY REVISIONS	MA	10/16/23
-	-	-	-
-	-	-	-

DESIGN AGENCY

OSBORN ENGINEERING

1111 Superior Avenue • Suite 2100 | Cleveland, OH 44114 (216)-861-2020
www.osborn-eng.com
1201 East Market Street • Suite 200 | Akron, OH 44305 (330)-535-3132

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE

MP 106.1 Cross Sections.dwg; 10/16/23 - 2:38pm



Sheet Totals	Cut	Fill
Seeding	162	4735

595

57

141

PROJECT 43-24-05

DATE: 06/30/23

NW/SW ROAD CROSS SECTIONS

NORTHWEST/SOUTHWEST ROAD OVER OHIO TURNPIKE

M.P. 106.1 **SANDUSKY AND ERIE COUNTIES**

DESIGNED	CHECKED
MA	DCA
DRAWN	IN CHARGE
MA	SMK

NO.	REVISIONS	BY	DATE
3	QUANTITY REVISIONS	MA	10/16/23
-	-	-	-
-	-	-	-

DESIGN AGENCY

OSBORN ENGINEERING

1111 Superior Avenue • Suite 2100 | Cleveland, OH 44114 (216)-861-2020 www.osborn-eng.com

1201 East Market Street • Suite 200 | Akron, OH 44305 (330)-535-3132

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE

MP 106.1 Cross Sections.dwg; 10/16/23 - 2:43pm



Sheet Totals	Cut	Fill
Seeding	211	245

479

58
141

PROJECT 43-24-05

DATE: 06/30/23

NW/SW ROAD CROSS SECTIONS
NORTHWEST/SOUTHWEST ROAD OVER OHIO TURNPIKE
M.P. 106.1 **SANDUSKY AND ERIE COUNTIES**

DESIGNED	CHECKED
MA	DCA
DRAWN	IN CHARGE
MA	SMK

NO.	REVISIONS	BY	DATE
3	QUANTITY REVISIONS	MA	10/16/23
-	-	-	-
-	-	-	-

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue • Suite 2100 | Cleveland, OH 44114 (216)-861-2020 www.osborn-eng.com
1201 East Market Street • Suite 200 | Akron, OH 44305 (330)-535-3132

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE



PLAN

(REAR ABUTMENT SHOWN, FORWARD ABUTMENT SIMILAR)



SECTION A-A



ABUTMENT SEAT ELEVATION

SEAT ELEVATIONS		
BEAM	REAR ABUTMENT	FORWARD ABUTMENT
A	710.54	710.51
B	710.66	710.66
C	710.72	710.80
D	710.61	710.71
E	710.48	710.59



SECTION B-B

FINAL ELEVATIONS		
POINT	REAR ABUTMENT	FORWARD ABUTMENT
A	714.37	714.42
B	714.61	714.66
C	714.42	714.48
D	714.22	714.28
E	714.46	714.52
F	714.28	714.34

NOTES:

1. FOR CHAIN LINK FENCE DETAILS, SEE OTIC STANDARD DRAWING CL-2.
2. FOR DECK JOINT DETAILS, SEE OTIC STANDARD DRAWINGS DJ-1, DJ-2, AND DJ-5.

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue - Suite 2100 | Cleveland, OH 44114 [216]481-5200
www.osborneng.com
1201 East Market Street - Suite 200 | Akron, OH 44305 [330]435-5132

NO.	REVISIONS	BY	DATE
3	OPTIONAL CJ	MD	10/16/23
-	-	-	-
-	-	-	-

DESIGNED	CHECKED
JDH	EIW
DRAWN	IN CHARGE
MJD	SMK

NW SW ROAD ABUTMENT PLAN
NORTHWEST/SOUTHWEST ROAD OVER OHIO TURNPIKE
SANDUSKY AND ERIE COUNTIES
M.P. 106.1

PROJECT 43-24-05
DATE: 06/30/23

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

MP 106.1 - Abutment Plan.dwg: 10/16/23 - 4:50pm

MP 106.8 - Cross Sections.dwg; 10/16/23 - 3:08pm



Sheet Totals	Seeding	Cut	Fill
	476	211	101

82
141

PROJECT 43-24-05

DATE: 06/30/23

STATE ROUTE 269 CROSS SECTIONS
STATE ROUTE 269 OVER OHIO TURNPIKE

M.P. 106.8 **ERIE COUNTY**

DESIGNED	CHECKED
DRP	DCA
DRAWN	IN CHARGE
DRP	SMK

NO.	REVISIONS	BY	DATE
3	QUANTITY REVISIONS	DR	10/16/23
-	-	-	-
-	-	-	-

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue • Suite 2100 | Cleveland, OH 44114 (216)-861-2020 www.osborn-eng.com
1201 East Market Street • Suite 200 | Akron, OH 44305 (330)-535-3132

OHIO TURNPIKE

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

OHIO TURNPIKE



SECTION A-A



SECTION B-B

NOTES :

1. FOR CHAIN LINK FENCE DETAILS, SEE OTIC STANDARD DRAWING CL-2
2. FOR DECK JOINT DETAILS, SEE OTIC STANDARD DRAWINGS DJ-1, DJ-2, AND DJ-5.
3. COMPACT FILL AS REQUIRED PER ODOT CMS 304. PAYMENT INCIDENTAL TO SP 202.

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue - Suite 2100 | Cleveland, OH 44114 (216)481-5200 www.osborneng.com
1201 East Market Street - Suite 200 | Akron, OH 44305 (330)435-5132

NO.	REVISIONS	BY	DATE
3	OPTIONAL CJ	MD	10/16/23
-	-	-	-
-	-	-	-

DESIGNED	CHECKED	DRAWN	IN CHARGE
MJD	JDH	MJD	SMK

SR 269 ABUTMENT PLAN - 2
STATE ROUTE 269 OVER OHIO TURNPIKE
ERIE COUNTY
M.P. 106.8

PROJECT 43-24-05
DATE: 06/30/23

10 / 18

104 / 141

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

MP 106.8 - Abutment Plan.dwg: 10/16/23 - 4:57pm



PLAN

(REAR ABUTMENT SHOWN, FORWARD ABUTMENT SIMILAR)



SECTION A-A



ABUTMENT SEAT ELEVATION

SEAT ELEVATIONS		
BEAM	REAR ABUTMENT	FORWARD ABUTMENT
A	725.99	725.95
B	726.01	725.99
C	726.12	726.10
D	726.03	726.02
E	725.98	726.00



SECTION B-B

SLAB ELEVATIONS		
POINT	REAR ABUTMENT	FORWARD ABUTMENT
A	730.00	729.67
B	730.23	729.90
C	730.03	729.71
D	729.86	729.71
E	730.09	729.73
F	729.90	729.54

NOTES :

1. FOR CHAIN LINK FENCE DETAILS, SEE OTIC STANDARD DRAWING CL-2
2. FOR DECK JOINT DETAILS, SEE OTIC STANDARD DRAWINGS DJ-1, DJ-2, AND DJ-5.
3. COMPACT FILL AS PER 304, PAYMENT INCINDENTAL TO SP202.

DESIGN AGENCY
OSBORN ENGINEERING
1111 Superior Avenue - Suite 2100 | Cleveland, OH 44114 (216)481-9200
www.osborneng.com
1201 East Market Street - Suite 200 | Akron, OH 44305 (330)435-9132

NO.	REVISIONS	BY	DATE
3	OPTIONAL CJ	MD	10/16/23
-	-	-	-
-	-	-	-
-	-	-	-

DESIGNED	CHECKED
MJD	JDH
DRAWN	IN CHARGE
MJD	SMK

DEYO ROAD ABUTMENT SLAB DETAILS
DEYO ROAD OVER OHIO TURNPIKE
ERIE COUNTY
M.P. 107.5

PROJECT 43-24-05
DATE: 06/30/23

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

MP 107.5 - Abutment Plan.dwg; 10/16/23 - 5:03pm