OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION

ADDENDUM NO. 10
ISSUED: JUNE 21, 2024

PROJECT NO. 43-24-09

BRIDGE REPLACEMENT & BRIDGE DECK REHABILITATION STATE ROUTE 88 OVER OHIO TURNPIKE M.P 199.5 OHIO TURNPIKE OVER BRYANT ROAD (TR 236) M.P. 202.8 OHIO TURNPIKE OVER NORTH MAIN STREET (CR 229) M.P. 203.7 PORTAGE COUNTY, OHIO

ISSUED MAY 3, 2024

OPENING DATE: 2:30 P.M. (EASTERN TIME) ~~MAY 24, 30~~ JUNE ~~4,~~ ~~5~~ ~~12~~ ~~20~~ 26, 2024

ATTENTION OF BIDDERS IS DIRECTED TO:

ANSWERS TO QUESTIONS RECEIVED THROUGH 11:00 A.M. ON JUNE 21, 2024

MODIFICATIONS TO THE CONTRACT DOCUMENTS

Revised Plan Sheets 12, 27, 65, 66, 67, 68, and 70 of 170

-AND-

Revised Estimated Quantities Worksheet Reference No's 117K, 117L

Issued by the Ohio Turnpike and Infrastructure Commission through Aimee W. Lane, Esq., Director of Contracts Administration.

Aimee W. Lane

Aimee W. Lane, Esq.
Director of Contracts Administration

June 21, 2024
Date

ANSWERS TO QUESTIONS RECEIVED THROUGH 11:00 A.M. ON JUNE 21, 2024:

Q#48 Note 8 on sheet 27/170 states …"INCLUDED IN THE LUMP SUM BID FOR ITEM 615 – PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A, AS PER PLAN". This item is not lump sum it has a quantity of 5374 SQ YD. Including a number of items unrelated to the number of square yards of temporary pavement being installed creates a problematic situation if the estimated quantity varies. Please add a lump sum bid item for 615 Roads for Maintaining Traffic for the unrelated items.

A#48 ~~*Note 8 on sheet 27 of 170 has been revised to the correct unit of "square yards" per Item 615 – Pavement for Maintaining Traffic, As Per Plan. The contractor shall bid this item to include all requirements per the plan note on sheet 12 of 170 and the details and notes provided on sheet 27 of 170. The revised sheet 27 of 170 has been provided with this addendum.*~~

A#48 (Revised)

Note 8 on sheet 27 of 170 has been revised to exclude the labor, equipment, and material costs associated with the removal of the temporary drainage per Item 615 – Pavement for Maintaining Traffic, As Per Plan. The contractor shall bid this item to include all requirements per the plan note on sheet 12 of 170 and the details and notes provided on sheet 27 of 170. The revised sheets 12 and 27 of 170 have been provided with this Addendum. Reference No. 117K - Item 611-Installation and Removal of 12" Slot Drain, Type 2, As Per Plan and Reference No. 117L - Item 611 - Installation and Removal of 12" Conduit, Type B, As Per Plan have been added to the Estimated Quantities Worksheet and provided in this Addendum.

Q#51 Based on the November start on SR-88, will the Turnpike allow traffic to be down to two lanes in both directions through the winter months?

A#51 All travel lanes of the turnpike mainline shall be open during the temporary winter shutdown period from November 15, 2024 to March 3, 2025 for MP 202.8 and MP 203.7. Refer to SP 103 E through G. Additionally see A#24 from Addendum No. 6 in regard to lane closures specific to MP 199.5.

END OF ADDENDUM NO. 10