OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION

ADDENDUM NO. 4
ISSUED JULY 23, 2020

PROJECT NO. 58-20-01 (REBID)

NEW MAINLINE TOLL PLAZA FACILITY
UTILITY BUILDINGS, TOLL BOOTHS & CANOPIES
MILEPOST 49
LUCAS COUNTY, OHIO

OPENING DATE: 2:00 P.M. (EASTERN TIME), JULY 28 ~~24~~, 2020
ALL BIDS MUST BE ELECTRONICALLY SUBMITTED

ATTENTION OF BIDDERS IS DIRECTED TO:
ANSWERS TO QUESTIONS RECEIVED THROUGH 5:00 P.M. ON JULY 22, 2020

MODIFICATIONS TO THE CONTRACT DOCUMENTS

Plan Sheets: C106, C107, and C119

-AND-

Approved Equals: 074519 and 042613

Issued by the Ohio Turnpike and Infrastructure Commission through Jennifer L. Stueber, Esq., General Counsel.

July 23, 2020

Jennifer L. Stueber, Esq., Date
General Counsel

ANSWERS TO QUESTIONS RECEIVED THROUGH 5:00 P.M. ON JULY 22, 2020:

Q#50 We have a warranty eligible contractor interested in providing a competitive bid using Mule-Hide's PVC roof system. Our PVC roof system meets or exceeds current ASTM standards and is equal to or superior in all respects to the specified product. Mule-Hide Products can also provide the same system warranty as specified. If you are still considering pre-bid product substitution requests for this project, I have attached our formal substitution request, along information about our products and company.

A#50 The proposed approved equal has been reviewed and the approval/disapproval action is included in the APPROVED EQUALS CHART below.

Q#51 In regards to Project 58-20-01 Milepost #49 New Mainline Toll Plaza Facility - we would like to request that County Materials Premier Ultra Burnished Ground Face units be considered as a possible Concrete Face Brick specification for this project. County Materials makes a high quality ground face block the meets the specification requirements, while providing a competitive price point. The completed substitution request form with data sheets, catalog information, and a photograph of the sample. Please advise if this is an approved equal?

A#51 The proposed approved equal has been reviewed and the approval/disapproval action is included in the APPROVED EQUALS CHART below.

Q#52 In addendum #2 plan HL-30.11 shows precast manholes with cast covers labeled as portland cement concrete manholes, while spec section 26 0543 calls out polymer "Quazite Box" style with tier ratings based on location. Which box is to be used for this project?

A#52 The Specifications shall be the governing Contract Document.

Q#53 Addendum 2 added various storm cleanouts, drain connections, and outlet pipes on plan sheets C106 and C107. Addendum 3 sheet C119 shows a standard clean-out detail using PVC pipe. What class of PVC pipe is to be used for the cleanout, and what types of pipes are permitted for the 2", 4" and 6" runs?

A#53 This Addendum No. 4 revises Plan Sheets C106, C107, and C119 to specify SDR 35 PVC for the miscellaneous drains.

APPROVED EQUALS CHART:

The following are modifications to the Approved Equals Chart for this Project with the issuance of Addendum No. 4:

COMPANY NAME	PRODUCT	SPECIFICATION	APPROVAL	Addendum
Mule-Hide	PVC Roofing	074519	Approved	4
County Materials	Burnished CMU	042613	Approved	4

Changes to the Specifications: Deletions are shown with strikethrough text.
Changes / Additions are shown with bold italicized text.

Changes to the Drawings: Additions and deletions are indicated with a cloud and revision triangle thus:

END OF ADDENDUM NO. 4