OHIO TURNPIKE AND
INFRASTRUCTURE COMMISSION

ADDENDUM NO. 4
ISSUED APRIL 22, 2021

PROJECT NO. 58-21-01

NEW MAINLINE TOLL PLAZA FACILITY
UTILITY BUILDINGS, TOLL BOOTHS & CANOPIES
MILEPOST 4
WILLIAMS COUNTY, OHIO
ISSUED MARCH 25, 2021

OPENING DATE: 2:00 P.M. (EASTERN TIME), APRIL *27* ~~22~~, 2021
ALL BIDS MUST BE ELECTRONICALLY SUBMITTED

ATTENTION OF BIDDERS IS DIRECTED TO:
ANSWERS TO QUESTIONS RECEIVED THROUGH 10:00 A.M. ON APRIL 22, 2021

Plan Sheets: I127

Issued by the Ohio Turnpike and Infrastructure Commission through Jennifer L. Stueber, Esq., General Counsel.

April 22, 2021

Jennifer L. Stueber, Esq., Date
General Counsel

ANSWERS TO QUESTIONS RECEIVED THROUGH 10:00 A.M. ON APRIL 22, 2021:

Q#77 Please reference drawing I127 Cable Schedule. Addendum no. 2 changed cable type 12 from #18- 5 Conductor to 8 Conductor. I do Not see cable type 12 used on drawing I127,128,129.

A#77 This Addendum revises Plan Sheet I127 (207) to revise cable type notes. All cable types are not used on every Plan Sheet, therefore Plan Sheets I128 and I129 do not have Cable Note 12.

Q#78 Please reference drawing I127 Cable Schedule. Cable type 10 is only being used in the upper two Barrier lanes, from the ATPM, but it does not show where it goes? Where does this connect to? Also, are these the only two locations for cable type 10?

A#78 This Addendum revises Plan Sheet I127 (207) to add Cable Note 10 to the other two ATPMs.

Q#79 Addendum 3, question 62 verified that the 6" casing pipe for the 2" sanitary force main ends at the limits of the boring. Can OTIC please verify the required limits for the 6" casing pipe needed for the 1.25" water service?

A#79 The 6" casing pipe for the 1.25" water service will end at the boring pit along with the 6" casing pipe for the 2" force main.

Changes to the Drawings: Additions and deletions are indicated with a cloud and revision triangle thus:

END OF ADDENDUM NO. 4