GENERAL SUMMARY

ITEM NO.	QUANTITY	UNIT	ITEM DESCRIPTION
			STRUCTURES
SP 202	1	LUMP	PORTIONS OF STRUCTURE REMOVED
503	1,254	CU. YD.	UNCLASSIFIED EXCAVATION
503	665	CU. YD.	ABUTMENT BACKFILL, AS PER 503.08
503	1	LUMP	COFFERDAMS AND EXCAVATION BRACING
505	1	LUMP	PILE DRIVING EQUIPMENT MOBILIZATION
507	4,235	FOOT	STEEL PILES, HP10X42, FURNISHED
507	3,615	FOOT	STEEL PILES, HP10X42, DRIVEN
507	124	EACH	STEEL POINTS OR SHOES
509	1,000	POUND	REINFORCING STEEL, REPLACEMENT OF EXISTING REINFORCING STEEL
SP 509	463,360	POUND	EPOXY COATED REINFORCING STEEL, GRADE 60
510	194	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT
511	465	CU. YD.	CLASS QC1 CONCRETE, ABUTMENT INCLUDING FOOTING
511	272	CU. YD.	CLASS QC1 CONCRETE, PIERS INCLUDING FOOTING
SP 511B	1,287	CU. YD.	CLASS HP4 CONCRETE, SUPERSTRUCTURE DECK SLAB
SP 511B	276	CU. YD.	CLASS S CONCRETE, BARRIERS AND PARAPETS, USING TYPE 1 CEMENT
SP 511B	276	CU. YD.	CLASS HP4 CONCRETE, ABUTMENT SLABS
SP 511B	1 8	CU. YD.	CLASS HP4 CONCRETE, FOR PREPLACEMENT TESTING
513	389,505	POUND	STRUCTURAL STEEL MEMBERS, LEVEL 3
SP 514A	1	LUMP	SURFACE PREPARATION OF EXISTING STEEL, SYSTEM OZEU
SP 514A	1	LUMP	FIELD PAINTING OF EXISTING STEEL, PRIME COAT, SYSTEM OZEU
SP 514A	1	LUMP	FIELD PAINTING OF NEW AND EXISTING STEEL, INTERMEDIATE COAT, SYSTEM OZEU
SP 514A	1	LUMP	FIELD PAINTING OF NEW AND EXISTING STEEL, FINISH COAT, SYSTEM OZEU
SP 514A	64	HOURS	REMEDIATION OF CHLORIDES
SP 514A	80	HOURS	GRINDING OF FINS, TEARS, SLIVERS
516	48	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE)
SP 516A	48	FOOT	CRACK REPAIR
SP 516B	2,450	FOOT	SEALING OF CONSTRUCTION JOINTS
SP 516G	60	EACH	REPLACE EXPANSION BEARING DEVICE
SP 516J	12	EACH	REPLACE FIXED BEARING DEVICE
SP 519	225	SQ. FT.	PATCHING OF CONCRETE STRUCTURES
SP 525A	1	LUMP	WORKER PROTECTION
SP 525A	40	EACH	PROTECTIVE CLOTHING/EQUIPMENT SET
SP 525A	1	LUMP	ESTABLISH REGULATED AREAS
SP 525A	1	LUMP	PAINT WASTE/HAZARDOUS WASTE CLASSIFICATION, HANDLING, AND DISPOSAL
SP 525A	1	LUMP	CONTAINMENT SYSTEM
SP 527	1	LUMP	FALSEWORK, TEMPORARY BRACING, AND PROTECTIVE STRUCTURES
SP 533	548	FOOT	THREE (3) INCH CONTINUOUS STRIP SEAL IN STRUCTURAL STEEL JOINT
SP 533A	164	FOOT	1 ½ INCH ELASTOMERIC COMPRESSION SEAL IN STRUCTURAL STEEL JOINT
SP 536	2,360	SQ. YD.	CONCRETE WEATHERPROOFING, SUBSTRUCTURE
SP 536	6,870	SQ. YD.	CONCRETE WEATHERPROOFING, DECK, ABUTMENT SLABS, AND APPROACH SLABS
601	1,260	SQ. YD.	CRUSHED AGGREGATE SLOPE PROTECTION

DESIGNED JAP | CHECKED HRB | DESIGN AGENCY ms consultants, inc. 2221 Schrock Road Columbus, Ohio 43229

DRAWN JDK | IN CHARGE HRB

NO.	REVISIONS	BY	DATE
1	ADDENDUM 3	JAP	09/20
-	-	-	-
-	-	-	-

GENERAL SUMMARY

PROJECT 43-20-03

DATE: 8/01/19

22 / 105

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

08350_GG001.dwg; 9/30/20 - 3:57pm