PLAN KEY NOTES

1. REMOVE AND REPLACE EXISTING TERRAZZO FLOOR INKIND.
2. NOT USED.
3. DEMO EXISTING CARPET AND PREPARE FOR NEW CARPET INSTALLATION. REFER TO I SHEETS FOR INSTALLATION DETAILS.
4. DEMO EXISTING TERRAZZO AND INSTALL NEW FLOORING. REFER TO I SHEETS FOR FINISH DETAILS.
5. ACCESS TO ALL AMENITIES IN THE SERVICE PLAZA ARE TO BE MAINTAINED FOR THE DURATION OF THE PROJECT. ALL WALKWAYS BEING MAINTAINED SHALL BE A MINIMUM OF 3' IN WIDTH. 1

LEGEND

- AREA OF NO NEW WORK.
- DEMO EXISTING TERRAZZO FLOOR FINISH
- DEMO EXISTING CARPET
- TERRAZZO COLOR NO. 1
- TERRAZZO COLOR NO. 2
- TERRAZZO COLOR NO.3
- TERRAZZO COLOR NO. 4
- TERRAZZO COLOR NO. 5

*NOTE ALL TERRAZZO COLOR AND CHIP TO MATCH EXISTING

1 TERAZZO DEMO FLOOR PLAN VERMILION VALLEY
3/32"=1'-0"

CHECKING PRINT
DATE: DATE: CORRECTED: DATE:
CHECKED: APPROVED: DATE:
DATE: DATE: BACKCHECKED: DATE:
DESIGNER
DRAWN

520 South Main Street
Akron, Ohio 44311
330.572.2100 Fax 330.572.2101
GPD GROUP
Giant Pyle Edwards Lund & Dittmore, Inc.

NO.	REVISIONS	BY	DATE
-	95% CD SUBMITTAL	-	02.26.20
-	BID DOCUMENTS REISSUED	-	08.20.20
1	ADDENDUM NO. 3	-	10.23.20

DESIGNED KLJ
DRAWN CT
CHECKED LMJ
IN CHARGE KLJ

LORAIN

TERAZZO DEMO FLOOR PLAN
VERMILION TERRACE

M.P. 139.5

PROJECT 53-20-02/03

SP5
ID-102

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION