ROOM FINISH SCHEDULE

NO.	NAME	WALL NORTH	WALL EAST	WALL SOUTH	WALL WEST	BASE	FLOOR	CEILING	REMARKS
200	AUTOMOBILE ENTRY	ETR	ETR	ETR	ETR	ETR	RFM-1	ETR	
201	PHONES	ETR	ETR	ETR	ETR	ETR	TRZ-1	ETR	
202	LOBBY SOUTH	ETR	ETR	ETR	ETR	ETR	ETR	ETR	NO NEW WORK
203	VENDING	ETR	ETR	ETR	ETR	ETR	ETR	ETR	NO NEW WORK
204	GIFT SHOP	ETR	ETR	ETR	ETR	ETR	ETR	ETR	NO NEW WORK
206	LOBBY NORTH	ETR	ETR	ETR	ETR	ETR	ETR 1	ETR	NO NEW WORK 1
207	AUTOMOBILE ENTRY	ETR	ETR	ETR	ETR	ETR	RFM-1	ETR	
209	WOMEN'S CORRIDOR	ETR	ETR	ETR	ETR	TB-1	ETR	ETR	
211	WOMEN'S WEST	ETR	ETR	ETR	ETR	TB-1	ETR	ETR	
212	WOMEN'S EAST	ETR	ETR	ETR	ETR	TB-1	ETR	ETR	
213	MEN'S CORRIDOR	ETR	ETR	ETR	ETR	TB-1	ETR	ETR	
214	MEN'S WEST	ETR	ETR	ETR	ETR	TB-1	ETR	ETR	
215	MEN'S EAST	ETR	ETR	ETR	ETR	TB-1	ETR	ETR	
216	INFORMATION CENTER	ETR	P-7	ETR	ETR	ETR	CPT-6	ACC-1, ACC-2	
217	FAMILY / UNISEX	WT-1	WT-1	WT-1	WT-1	TB-2	FT-1	ETR	
218	TRUCKER LOBBY	PT-6	N/A	PT-6	PT-6	TB-1	ETR	ETR	
219	TRUCKER'S ENTRY	ETR	ETR	ETR	ETR	ETR	RFM-1	ETR	
220	TRUCKER'S LOUNGE	PT-6	PT-5	PT-6	N/A	RWB-1	CPT-1, CPT-2	ACT-1	
221	COMMUNITY ROOM	PT-6	PT-5	PT-5	PT-6	RWB-1	CPT-3, -4, -5	ACT-1	
222	LAUNDRY	PT-6	FRP-1	PT-6	PT-6	TB-2	FT-1	ACT-1	
223	CORRIDOR	PT-6	PT-6	PT-6	PT-6	TB-2	FT-1	ACT-1	
224	TRUCKER TOILET/SHOWER ROOM	WT-1	WT-1	WT-1	WT-1	TB-1	FT-1	GYP-1	WT-2B WHERE NOTED
225	TRUCKER TOILET/SHOWER ROOM	WT-1	WT-1	WT-1	WT-1	TB-1	FT-1	GYP-1	WT-2A WHERE NOTED
226	TRUCKER TOILET/SHOWER ROOM	WT-1	WT-1	WT-1	WT-1	TB-1	FT--1	GYP-1	WT-2C WHERE NOTED
227	TRUCKER TOILET/SHOWER ROOM	WT-1	WT-1	WT-1	WT-1	TB-1	FT-1	GYP-1	WT-2D WHERE NOTED
238	CORRIDOR	ETR	ETR	ETR	ETR	ETR	TRZ-1	ETR	
246	FOOD SERVICE	ETR	ETR	ETR	ETR	ETR	ETR	ETR	NO NEW WORK
247	FOOD COURT	ETR	ETR	ETR	ETR	ETR	ETR	ETR	NO NEW WORK
248	BUS ENTRY	ETR	ETR	ETR	ETR	ETR	RFM-1	ETR	

TOILET ACCESSORY SCHEDULE

CODE	TYPE	MANUFACTURER	MODEL #	COLOR / TYPE	LOCATION
PTD-1	RECESSED PAPER TOWEL DISPENSER	BOBRICK	2447	N/A	GROUP RR -OPT 1
PTD-2	RECESSED PAPER TOWEL DISPENSER	BOBRICK	B-359033	N/A	TYP. TRUCKER RR
PTD-3	CASEWORK LAMINATE	BOBRICK	B-3803	N/A	ACCESSIBLE TRUCKER RR
TPD-1	WOMEN'S / UNISEX TOILET PAPER DISPENSER	BOBRICK	B-35745	N/A	GROUP RR
TPD-2	MEN'S TOILET PAPER DISPENSER	BOBRICK	B-34745	N/A	TRUCKER RR
SD-1	COUNTER MANUAL SOAP DISPENSER	BOBRICK	B-8221	N/A	GROUP RR
SD-2	COUNTER AUTOMATIC SOAP DISPENSER	TECHNICAL CONCEPTS	401310	N/A	ALL TRUCKER RR
SD-3	WALL SOAP DISPENSER	BOBRICK	B-2111	N/A	FAMILY RR
CT-1	CHANGING TABLE	ASI	9014	GRAY	FAMILY RR
CS-1	CHILD SEAT	KOALA KARE	KB102-01	GRAY	FAMILY RR
M-1	ADA TILE W/SHELF MIRROR	BOBRICK	7405-18"Wx30"H-2	N/A	FAMILY RR
M-2	TYP. MIRROR	BOBRICK	B-290 1842	N/A	GROUP RR
M-3	ADA TRUCKER SHOWER	BOBRICK	B-290 3042	N/A	ACCESSIBLE TRUCKER RR
M-4	TYP. TRUCKER MIRROR	BOBRICK	B-290 4842	N/A	TYP. TRUCKER SHOWER
SHS-1	SHOWER SEAT	BOBRICK	B-5181	N/A	ACCESSIBLE TRUCKER RR
SC-1	SHOWER CURTAIN	BOBRICK	204-2	42"W x 72"H	ALL TRUCKER RR
SCH-1	SHOWER CURTAIN HOOKS	BOBRICK	240-1	N/A	ALL TRUCKER RR
SCR-1	ADA SHOWER CURTAIN ROD	AMERICAN SPECIALTIES	1214-036	N/A	ACCESSIBLE TRUCKER RR
SCR-2	SHOWER CURTAIN ROD	AMERICAN SPECIALTIES	1214-030	N/A	ALL TRUCKER RR

GENERAL NOTES

1. GC TO REFERENCE PLAN NORTH FOR ALL FINISH APPLICATIONS NOTED IN ROOM FINISH SCHEDULE.
2. ALL EXISTING WALLS TO BE REPAINTED IN SAME COLOR TO MATCH EXISTING, U.N.O.

STATE OF OHIO
MARK STEPHEN SALOPEK
8875
REGISTERED ARCHITECT

Mark S. Salopek License #8875

Expiration Date December 31, 2021

MATERIAL FINISH SCHEDULE

CODE	MATERIAL	SPECIFICATION SECTION	MANUFACTURER	COLLECTION	TYPE	COLOR	SIZE	LOCATION	REMARKS
BASE									
TB-1	TILE BASE	09 30 13	TBD	TBD	TBD	TBD	TBD	GROUP RESTROOMS + CORRIDORS	GROUT COLOR AND JOINT SIZE TO MATCH EXISTING CONDITIONS
TB-2	TILE BASE	09 30 13	DALTILE	AMBASSADOR LIGHT POLISHED	S-36C9T COVE BASE	AM36 WANDERLUST WHITE	6" X 12"	ALL TRUCKER SHOWERS	ALL TRUCKER SHOWERS
RWB-1	RUBBER BASE	09 65 13	JOHNSONITE	BASEWORKS	TYP. COVE BASE	199 DOCKSIDE	4" H. ROLL GOODS	TRUCKER LOUNGE, MEETING CENTER	TRUCKER LOUNGE, MEETING CENTER
CASEWORK									
PL-1	CASEWORK LAMINATE	12 32 16	WILSONART	N/A	FINEGRAIN FINISH	8223K-12 BLACKENED CHESTNUT	N/A	INFORMATION DESK	
PL-2A	CASEWORK LAMINATE	12 32 16	FORMICA	COLOR CORE 2	MATTE FINISH	7223C-58 NEW WHITE	N/A	MENS AND WOMENS RESTROOMS	
PL-2B	CASEWORK LAMINATE	12 32 16	WILSONART	N/A	MATTE FINISH	D388-60 CRYSTAL	N/A	MENS AND WOMENS RESTROOMS	VE ALTERNATE FOR PL-2A
PL-3	CASEWORK LAMINATE	12 32 16	WILSONART	N/A	LINEARITY FINISH	7960K-18 STUDIO TEAK	N/A	MEETING CENTER	
QTZ-1	QUARTZ COUNTER	12 36 61.19	TBD	TBD	TBD	TBD	TBD	INFORMATION DESK, MEETING CENTER	TO RECEIVE EASED PENCIL EDGE
SS-1	SOLID SURFACE COUNTER	12 36 61.16	TBD	TBD	TBD	TBD	TBD	INFORMATION DESK, MEETING CENTER	TO RECEIVE EASED PENCIL EDGE; VE ALTERNATE FOR QTZ-1
SS-2	SOLID SURFACE COUNTER	12 36 61.16	WILSONART	N/A	9228SS	CHILLED EARTH	N/A	MENS AND WOMENS RESTROOMS, TRUCKER SHOWERS	
CEILING									
ACT-1	ACOUSTIC CEILING TILE	09 51 13	USG	FROST #418	FINELINE GRID	WHITE	2' X 2' X 3/4"	TRUCKER LOBBY, TRUCKER LOUNGE, MEETING CENTER	NEW AND INFILL EXISTING AS REQUIRED THROUGHOUT SCOPE
PT-1	CEILING PAINT	09 91 00	SHERWIN WILLIAMS	N/A	N/A	SW 7005 PURE WHITE	N/A	ALL CEILINGS , UNO	NEW AND REPAIRED CEILINGS THROUGHOUT SCOPE
ACC-1	ACOUSTIC CEILING CLOUD	09 84 36	ARKTURA	SOFTGRID	SCALE	WHISPER	(2) 7'-6" X 7'-6" MODULES	INFORMATION CENTER	SEE A-112 FOR ADD'L DETAILS
ACC-2	ACCOUSTIC CEILING CLOUD	09 84 36	ARKTURA	SOFTGRID	SCALE	SAND	(3) 7'-6" X 7'-6" MODULES	INFORMATION CENTER	SEE A-112 FOR ADD'L DETAILS
FLOORS									
CPT-1	FLOCKED VINYL PLANK	09 68 13	FORBO	FLOTEX MODULAR	BOX CROSS	133002 PEARL	25 CM X 100 CM	TRUCKER LOUNGE	RANDOM BRICK INSTALL; SEE I-103 FOR ADD'L DETAILS
CPT-2	FLOCKED VINYL PLANK	09 68 13	FORBO	FLOTEX MODULAR	BOX CROSS	133007 GRANITE	25 CM X 100 CM	TRUCKER LOUNGE	RANDOM BRICK INSTALL; SEE I-103 FOR ADD'L DETAILS
CPT-3	FLOCKED VINYL PLANK	09 68 13	FORBO	FLOTEX MODULAR	METRO	946006 GREY	25 CM X 100 CM	MEETING CENTER	MONOLITHIC INSTALL; SEE I-103 FOR ADD'L DETAILS
CPT-4	FLOCKED VINYL PLANK	09 68 13	FORBO	FLOTEX MODULAR	METRO	946024 CARBON	25 CM X 100 CM	MEETING CENTER	MONOLITHIC INSTALL; SEE I-103 FOR ADD'L DETAILS
CPT-5	FLOCKED VINYL PLANK	09 68 13	FORBO	FLOTEX MODULAR	METRO	946039 ANTHRACITE	25 CM X 100 CM	MEETING CENTER	MONOLITHIC INSTALL; SEE I-103 FOR ADD'L DETAILS
FT-1	FLOOR TILE	09 30 13	DALTILE	AMBASSADOR	UNPOLISHED	AM35 GLOBAL GREY	N/A	ALL TRUCKER SHOWERS	FULL HEIGHT TO CEILING
FT-2A	FLOOR TILE	09 30 13	CROSSVILLE	RETRO ACTIVE 2.0	UNPOLISHED	RET08 MERCURIAL	N/A	TRUCKER SHOWER 225	ACCENT BAND AS NOTED IN ELEVATIONS
FT-2B	FLOOR TILE	09 30 13	CROSSVILLE	RETRO ACTIVE 2.0	UNPOLISHED	RET10 ARMOR	N/A	TRUCKER SHOWER 224	ACCENT BAND AS NOTED IN ELEVATIONS
FT-2C	FLOOR TILE	09 30 13	CROSSVILLE	RETRO ACTIVE 2.0	UNPOLISHED	RET12 RACING GREEN	N/A	TRUCKER SHOWER 226	ACCENT BAND AS NOTED IN ELEVATIONS
FT-2D	FLOOR TILE	09 30 13	CROSSVILLE	RETRO ACTIVE 2.0	UNPOLISHED	RET13 ROYAL NAVY	TBD	TRUCKER SHOWER 227	ACCENT BAND AS NOTED IN ELEVATIONS
RFM-1	RECESSED FLOOR MAT	09 68 13	TBD	TBD	TBD	DEEP FINISH ANNODIZED ALUMINUM FRAME; MIDNIGHT HEAVY DUTY-GRADE CARPET INSERTS	MATCH EXISTING	ENTRY VESTIBULES WHERE EXISTING	REPLACE EXISTING IN KIND
TRZ-1	THIN SET EPOXY TERRAZZO	09 66 23.16	EXISTING	EXISTING	EXISTING	EXISTING	N/A	THROUGHOUT SCOPE	REFERENCE XX SHEET XX FOR ADDITIONAL DETAILS
WALLS									
FRP-1	FIBERGLASS REINFORCED PANEL	10 26 00	CRANE COMPOSITES	GLASBORD	EMBOSSED	WHITE	N/A	LAUNDRY ROOM ONLY	
PT-2	PAINT	09 91 00	SHERWIN WILLIAMS	N/A	N/A	SW 6126 NAVAJO WHITE	N/A	THROUGHOUT SCOPE	OVERALL PAINT WHERE NOTED
PT-3	PAINT	09 91 00	SHERWIN WILLIAMS	N/A	N/A	SW 6201 THUNDEROUS	N/A	THROUGHOUT SCOPE	ACCENT PAINT WHERE NOTED
PT-4	PAINT	09 91 00	SHERWIN WILLIAMS	N/A	N/A	SW 6545 MAJESTIC PURPLE	TBD	THROUGHOUT SCOPE	ACCENT PAINT WHERE NOTED
PT-5	PAINT	09 91 00	SHERWIN WILLIAMS	N/A	N/A	SW 7016 MINDFUL GRAY	TBD	THROUGHOUT SCOPE	ACCENT PAINT WHERE NOTED, DOORS AND FRAMES AS NOTED
PT-6	PAINT	09 91 00	SHERWIN WILLIAMS	N/A	N/A	SW 7005 PURE WHITE	N/A	THROUGHOUT SCOPE	OVERALL PAINT WHERE NOTED
PT-7	PAINT	09 91 00	SHERWIN WILLIAMS	N/A	N/A	SW 9161 DUSTBLU	N/A	THROUGHOUT SCOPE	ACCENT PAINT WHERE NOTED
WT-1	WALL TILE	09 30 13	DALTILE	AMBASSADOR	LIGHT POLISHED	AM36 WANDERLUST WHITE	12" X 24"	ALL TRUCKER SHOWERS	
WT-2A	WALL TILE	09 30 13	CROSSVILLE	RETRO ACTIVE 2.0	PATTERN	RET08 MERCURIAL	6" X 24"	TRUCKER SHOWER 225	ACCENT STRIPE AS NOTED
WT-2B	WALL TILE	09 30 13	CROSSVILLE	RETRO ACTIVE 2.0	PATTERN	RET10 ARMOR	6" X 24"	TRUCKER SHOWER 224	ACCENT STRIPE AS NOTED
WT-2C	WALL TILE	09 30 13	CROSSVILLE	RETRO ACTIVE 2.0	PATTERN	RET12 RACING GREEN	6" X 24"	TRUCKER SHOWER 226	ACCENT STRIPE AS NOTED
WT-2D	WALL TILE	09 30 13	CROSSVILLE	RETRO ACTIVE 2.0	PATTERN	RET13 ROYAL NAVY	6" X 24"	TRUCKER SHOWER 227	ACCENT STRIPE AS NOTED

CHECKING PRINT
DESIGNER DATE: CHECKED: DATE: CORRECTED: DATE:
DRAWN DATE: BACKCHECKED: DATE: APPROVED: DATE:

520 South Main Street
Suite 2441, Akron, OH 44311
330.572.2100 Fax 330.572.2101
GPD GROUP
Gates, Pyle, Salomon, Burns & Dykstra, Inc.

NO.	REVISIONS	BY	DATE
-	95% CD SUBMITTAL	-	02.26.20
-	BID DOCUMENTS REISSUED	-	08.20.20
1	ADDENDUM NO. 3	-	10.23.20

DESIGNED KEC | CHECKED LMJ
DRAWN KEC | IN CHARGE KLJ

LORAIN

INTERIOR FINISH SCHEDULE

M.P. 139.5

PROJECT 53-20-02/03

SP5
I-601

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION